

**Tender Schedule for the work : Estimate for the Construction of Paddy Procurement Platfrom At Main Market Yard, R.M.C, Bhadrak.**

**Tender Value : Rs. 4,56,794.00**

<b>Sl. No.</b>	<b>Item of Work</b>	<b>Unit</b>	<b>Qty.</b>	<b>Rate</b>	<b>Amount</b>
1.	Excavation in hard soil of foundation with initial lead and lift.	One cum	26.31	52	Rs. 1,696.00
2.	Filling sand in F&P with well watered and rammed including cost, conveyance, royalties etc. complete.	One cum	241.72	450.50	Rs. 1,08,895.00
3.	C.C in (1:3:6) using 4cm size c.b.h.g metal including cost, conveyance, royalties etc. complete.	One cum	35.92	3202	Rs. 1,15,016.00
4.	Well burnt K.B. brick masonry in cm (1:6) in F&P including cost, conveyance, royalties etc. complete.	One cum	55.45	2614.10	Rs. 1,44,952.00

**No. of Correction**

**No. of Over Writing**

**Signature of the contractor**

**Chairman R.M.C, Bhadrak**

Sl. No.	Item of Work	Unit	Qty.	Rate	Amount
5.	C.C in (1:½:3) using 12mm or cbhg chips including cost, conveyance, royalties etc. complete. With punning.	One cum	16.87	4726.70	Rs. 79,739.00
6.	16mm thick cement plaster in (1:6) over wall including cost, conveyance, royalties etc. complete	One sqm	81	80.20	Rs. 6,496.00
				<b>Total -</b>	<b>Rs. 4,56,794.00</b>

Six Nos. Items only

Percentage of Less \_\_\_\_\_ % Less

Percentage of Excess \_\_\_\_\_ % Excess

Jr. Engineer  
OSAM Board, BBSR.

Asst. Engineer  
OSAM Board, BBSR

Secretary  
R.M.C, Bhadrak

Chairman,  
R.M.C., Bhadrak