

## Tender Schedule for the work : Improvement of Black Topping Approach Road at Main Market Yard, Bhadrak

Tender Value : Rs. 8,50,568.00

Sl. No.	Item of Work	Unit	Qty.	Rate	Amount
1.	labour for spreading morrum and consideration with PRR including watering but excluding cost conveyance of morum.	One cum	420	125.77	Rs. 52,823.00
2.	Labour for spreading 4cm size cbhg metal in proper chamber and consolisation with PRR including watering and forsedsing.	One cum	240	189.22	45,413.00
3.	Collection of moorum (measuring 1.5 x 1.5 x 0.5= 1cum) including cost, conveyance, royalties etc complete.	Nos.	420	573	2,40,660.00
4.	Collecting of 4cm size cbhg meal including cost, conveyance, royalties etc complete.	Nos	240	1109.40	Rs 2,66,256.00

**No. of Correction**

**No. of Over Writing**

**Signature of the contractor**

**Chairman R.M.C, Bhadrak**

Sl. No.	Item of Work	Unit	Qty.	Rate	Amount
5.	Labour for 40mm thick premix carpet using 0.23 of 13.20 of 6mm size chip with 12.70kg of bitumen for 9.29 sqm. Including hire and running charges or PRR.	One Sqm	1200	20.76	Rs. 24,912.00
6.	Labour for laying 6mm thick precoated seal coat.	One Sqm.	1200	10.20	12,240.00
7.	Collection of 20mm to 12mm down graded cbhg chips	One cum	48.00	1289.40	Rs. 61,891.00
8.	Collection of 6mm size cbhs bajuri chips	One cum	7.20	1119.40	Rs. 8059.00
9.	Coat of bitumen 40qtl. @ Rs. 3400/qtl.	Qtl.	40	3400	Rs. 1,36,000.00
10.	Transport charges of P.R.R				<u>Rs 2,314.00</u>
					<b>Rs.8,50,568.00</b>

Ten Nos. Items only

Percentage of Less \_\_\_\_\_ % Less

Percentage of Excess \_\_\_\_\_ % Excess

Jr. Engineer  
OSAM Board, BBSR.

Asst. Engineer  
OSAM Board, BBSR

Secretary  
R.M.C, Bhadrak

Chairman,  
R.M.C., Bhadrak